DIVISION 4 MASONRY

04 20 00 Unit Masonry

PART 1: GENERAL

1.01 Scope of Standard

- A. This standard provides general guidance concerning the specific preferences of the Texas State University for manufactured units of masonry, both load bearing and non-load bearing.
- B. Texas State University recognizes that project conditions and requirements vary, thus precluding the absolute adherence to the items identified herein in all cases. However, unless there is adequate written justification, it is expected that these guidelines will govern the design and specifications for Texas State University projects.

1.02 Design Guidelines

- A. Unity Through Design Expression: San Marcos Campus
 - 1. As the major design tool in the creation of unity among Texas State University campus buildings, employ brick masonry as the predominant exterior building material, with stone or precast concrete door and window lintels/sills, and with stone or precast concrete floor articulated courses. Refer to the 2006-2017 Master Plan for design guidelines.
 - The strength and appeal of this basic material are universal. Repeat the use of face brick of tan color and of velour texture to match brick masonry of recently constructed Texas State University buildings.
- B. Unity Through Design Expression: Round Rock Campus
 - As the major design tool in the creation of unity among Texas State University-Round Rock campus buildings, employ brick masonry and chopped limestone as the predominant exterior building material.
 - 2. Repeat the use of face brick of tan color and chopped limestone, with punched windows, to match the character of the Avery Building.

C. Brick Masonry Approval

- 1. Early in the construction phase, before the material is installed, secure University approval of samples and sample panels of actual brick, or other material, proposed for installation on the new building's exterior walls.
- 2. Contractor shall be required to construct a sample panel (8' L. X 6' H. minimum) showing brick and mortar color and any other materials (stone, plaster, cap flashing, window, etc.)
- 3. The contractor shall allow a minimum 6 weeks review rework and approval of the sample panel before ordering brick.

- 4. Locate in full sun & as directed by Texas State University representative.
- 5. Mock up will be constructed no later than 3 months prior to needing masonry delivered to the construction site.
- 6. Deviation from Brick. If, in the design of a new building, the architect proposes a deviation from the brick masonry envelope described above, Texas State University must approve such deviation in writing

1.03 Reference Standards

- A. Reinforced Grouted Brick Masonry, Masonry Institute of America
- B. Masonry Veneer (Second Edition), Masonry Institute of America
- C. Reinforced Masonry Engineering Handbook (Fifth Edition Updated), Masonry Institute of America.
- D. 1997 Masonry Codes and Specifications, Masonry Institute of America
- E. Reinforcing Steel in Masonry, Masonry Institute of America
- F. Technical Notes on Brick Construction, Brick Industry Association
- G. The Secretary of the Interior's Standards for the Treatment of Historic Properties 1995, U.S. Dept. of the Interior, National Park Service.

PART 2: PRODUCTS

2.01 Brick Veneer:

- A. San Marcos Campus:
 - 1. Brick: To match Acme Brick Company "Doeskin Elgin 186" blend-modular, velour texture (Project Code 151860121)
 - Accent Brick: Acme Brick, 138, Royal Brikdale, R#035504, Denton, TX, Product Code 29-238-01-27
 - a. To be used only as accent brick course(s) on perimeter brick monument signs and fence columns.
- B. Round Rock Campus: (Avery Building)
 - 1. Brick: To match "Painted Desert #230", Velour face, as manufactured by Acme Brick (Project Code 152300121)-modular.
 - 2. Stone: To match "Austin Cream Stone" Tan Limestone, dimensioned chapped-face limestone from Gamboa Quarry, Liberty Hill, Texas: nominal 12" X 24", and matching cast stone lintels.


- C. Consultant shall arrange to bring brick supplier into the design process early to verify any new developments in brick production that may impact brick unit appearance or delivery.
- D. New masonry used in renovation work is to match the masonry of the existing building.
- E. Grout: Coordinate color of mortar with the Texas State University project representative. Use only a pre-mixed mortar, with no calcium chloride admixtures.
 - 1. San Marcos Campus: Spectrum, Eldridge Buff color.
- F. Repointing should occur in advance of cleaning, unless authorized by Texas State University project representative.

2.02 Sign Letters

- 1. The "Texas State University" letters are 8" high, all upper case, Times Bold, font, 1" return, dark bronze anodized aluminum, water jet cut.
- 2. The "Established 1899" letters are 4" high, all upper case, Times Bold, font, 1" return, dark bronze anodized aluminum, water jet cut.
- 2.03 Perimeter Campus Brick Columns (San Marcos): Refer to Exhibits 1 & 2
- 2.04 Perimeter Campus Brick Monument Signs (San Marcos): Refer to Exhibits 1-10.
- 2.05 Sealer: Same as sealer under Unit Masonry Cleaning & Restoration

PART 3: EXECUTION: (NOT USED)

END OF SECTION 04 20 00



File updated: 5/28/2013


7 78666-4616 Fax (512)245-8839 File name: Brick Column Standard

Plot Date: 6/6/2013




601 University Drive San Marcos, Texas 78666 Phone: (512)245-2202 Fax (5 of 2


Exhibit 1A:





Column Cap Detail
1/2" = 1'-0"


TEXAS	Title:Column Cap Detail	Sheet No.:
I San Marcos, Texas 78666-4616 I	File updated: 4/22/2009 Plot Date: 5/28/2013 File name:Brick Column Standard	2 of 2




























Exhibit 12: Cast stone, Continental cast stone, #1101-T, "Greystone". 9 $+1'-11\frac{1}{2}"$ Elevation Field verify radius of wall for cap dimension Max. Plan Precast Wall Cap A Scale: 1" = 1'-0"

TEXAS	Title: Campus Standard Monument Sign	Sheet No.:
STATE 601 University Drive San Marcos, Texas 78666-4616 Phone: (512)245-2202 Fax (512)245-8839	File updated: 6/6/2013 Plot Date: 6/6/2013 File name: StandardMonumentSign1.dwg	10 of 12

Exhibit 13:





Field verify radius of wall for cap dimension

Precast Wall Cap B

Scale: 1" = 1'-0"

TEXAS	Title: Campus Standard Monument Sign	Sheet No.:
601 University Drive San Marcos, Texas 78666-4616 Phone: (512)245-2202 Fax (512)245-8839	File updated: 6/6/2013 Plot Date: 6/6/2013 File name: StandardMonumentSign1.dwg	11 of 12

